

NOTICE INVITING TENDER (Re- Tender)

Sealed item rate quotations are invited for **Work of Laying 2 inch HDPE Hose and 1 inch/ 1.5 inch HDPE hose from campus 1 to campus 2 for water line and OFC line in NIELIT, Calicut.** The quotations are invited in duplicate, subscribed on the envelope with the reference No. and due date. The quotations as accompanied with EMD of **Rs. 15000/- (Rupees fifteen thousand only)** in the form of Online deposit slip / Net banking or demand draft drawn in favour of the Director, National Institute of Electronics and Information Technology, Calicut, payable at State Bank of India, NITC Branch, should reach to the office of the Director, National Institute of Electronics and Information Technology, NIT Campus Post, Calicut-673601, **On or before 20-11-2018** and will be opened at **2.00 PM on 21-11-2018**, in the presence of the tenderers who wish to be present. The Quotation not accompanied with EMD shall be rejected. [Terms and conditions attached](#)

For DIRECTOR

Encl: 1. Schedule of work
2. Terms and conditions

SCHEDULE FOR THE WORK OF LAYING 2 INCH HDPE HOSE AND 1 INCH/ 1.5 INCH HDPE HOSE FROM CAMPUS 1 TO CAMPUS 2 FOR WATER LINE AND OFC LINE IN NIELIT, CALICUT. (Re-Tender)

SI No	Description of item	Qty.	Unit	Per metre Rate
1	Excavation of trench for laying 2 inch HDPE Hose and 1 inch / 1.5 inch HDPE hose from campus 1 to campus 2 as per the instructions from the Departmental Officer In-charge , including cleaning of all obstructions & jungle bushes on the excavating path, including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m, including cost and conveyance of all materials labours etc complete	1300 (approx.)	m	
	a) Soil area	1	m	
	b) Ordinary rock area	1	m	

- ❖ Contractors are requested to quote for running metre rates
- ❖ Approx. quantity of excavation & laying is 1300 metre. Actual quantity may vary based on running metre measurement
- ❖ NB: Contractor may visit the site and inspect before quoting to know the actual conditions of excavation path
- ❖ Around 160 meters of excavation is in PWD premises, official permission from PWD side will be obtained by NIELIT

For National Institute of Electronics and Information
Technology, Calicut

Date:

Signature of the Contractor:
Name, Address & Contact Details

Date: