



राष्ट्रीय इलेक्ट्रॉनिकी एवं सूचना प्रौद्योगिकी संस्थान NATIONAL INSTITUTE OF ELECTRONICS AND INFORMATION TECHNOLOGY

(आई एस ओ 9001:2008 प्रमाणित) (ISO 9001:2008 CERTIFIED)

(इलेक्ट्रॉनिकी और सूचना प्रौद्योगिकी मंत्रालय, भारत सरकार की एक स्वायत्त वैज्ञानिक संस्था)

(Autonomous Scientific Society of Ministry of Electronics and Information Technology, Government of India)

पी.बी. नं. 5, एन.आई.टी. कैम्पस पोस्ट, कालिकट - 673601, केरल, भारत P.B. No. 5, NIT Campus Post, CALICUT - 673 601, KERALA, INDIA

Phone : (0495) 2287266, Fax : (0495) 2287168, Web : <http://nielit.gov.in/calicut>

5(137) / 2022 / SMART LAB SETUP

Date: 09-03-2023

NOTICE INVITING TENDER

Sealed item rate quotations are invited for **Providing Acoustic Panelling and Electrical wiring requirements for content creation for Smart Lab Project in Room no.: 225, NIELIT Main campus.** The work to be subscribed on the envelope with the reference No. and due date. The quotations as accompanied with EMD of **Rs. 11,750/- (Rupees Eleven Thousand Seven Hundred and Fifty Only)** in the form of Online deposit slip/ Net banking/ CDM deposit to NIELIT account (**Account No.: 10401158037, SBI NITC Branch, IFSC SBIN0002207**) or demand draft drawn in favour of the Executive Director, National Institute of Electronics and Information Technology, Calicut (payable at State Bank of India, NITC Branch) should reach to the office of the Director, National Institute of Electronics and Information Technology, NIT Campus Post, Calicut-673601, **On or before 5.00 pm of 16-03-2023** and will be opened on **17-03-2023, 2.00 pm** in the presence of the tenderers who wish to be present.


DIRECTOR

- Encl: 1. Schedule of work
2. Terms and conditions

TERMS & CONDITIONS FOR WORKS

CDS/CA/6.3.0/F 07/R3

1. The quotation shall be in the prescribed form and shall be valid for a minimum period of three months from date of its opening. Should the tenderer modify or withdraw his quotations within the said period of 3 months, from the date of its opening, the earnest money deposited by the tenderer shall be forfeited.
2. The Director shall be the Accepting officer, hereinafter referred to as such, for the purpose of the contract.
3. All rates shall be quoted in the prescribed form.
4. All the rates must be filled-in, in both words and figures.
5. The quotations shall be accompanied by the Earnest Money of **Rs.11,750/-** in the form of Online deposit proof / Net banking or demand draft drawn in favour of the Director, National Institute of Electronics and Information Technology, Calicut, payable at State Bank of India, NITC Branch.
6. On acceptance of the quotation, earnest money will be treated as part of the Security Deposit. Failure of the successful tenderer to carry out the quoted work shall entail in forfeiture of the total earnest money/security deposit.
7. The amount of security deposit including the amount of earnest money shall be 5% of the tendered cost of the work. Upon acceptance of the quotation, the successful tenderer shall within 10 days of the written acceptance of his quotation, deposit with NIELIT, Calicut an amount equivalent to 5% of the value of the works at the accepted rates.
8. NIELIT Calicut will return the earnest money without any interest to unsuccessful tenderers.
9. The time of completion of the work shall be by **30 Days**.
10. In case the Contractor fails to complete the work on or before the stipulated completion time, he shall be liable to pay 1% of the total order value as liquidated damages for each day of default.
11. If the work cannot be completed within the stipulated completion time due to any unforeseen or unavoidable reasons beyond the control of the Contractor, he shall seek prior permission from the Competent Authority, well before the stipulated completion time itself, for delayed execution of the work, clearly stating the reasons for delay as well as fresh date of completion.
12. There will be 15 days' time from the date of issue of the acceptance letter for commencement of work.
13. The defect liability period will be of **One Year** duration, upon satisfactory completion of which, the security deposit will be refunded to the tenderer.
14. The tenderer is required to comply with the provision of all the Acts/legislations of the Govt. relating to the Labor laws, and the rules and regulations made there under from time to time and to submit at the proper time, all particulars and statements required to be furnished to the Labor authorities concerned.
15. The tenderer shall give all necessary personal superintendence during the execution of the works.
16. No materials shall be supplied by NIELIT Calicut except those mentioned.
17. The contractor shall make his own arrangements for water and electricity required for the work and nothing extra will be paid to him for the same. If the contractor is unable to make his own arrangements, on written request, the Centre may consider water supply for the work and 1% of the value of the total work done towards water charge shall be deducted from the bill.
18. Payment shall be released after satisfactory completion of the work. The work is to be carried out in accordance with the CPWD specifications, rules and regulations.
19. The successful tenderer, within one week of award of the work to him shall submit to the Director an illustrative and suitable colored work-time chart.
20. The materials to be used in electrical installations shall be of approved make and quality as specified in the schedule of quantities and shall conform strictly to the relevant Indian Standard Specifications.

TERMS & CONDITIONS FOR WORKS

21. (1) During the execution of work, unless otherwise specified, the contractor shall at his own cost provide the materials and execute all shoring, timbering and structures, excavations and works and shall ensure that no damage, injury or loss is caused or is likely to be caused to any person or property.
- (2) The Contractor shall be responsible to take all precautions to ensure the safety of the public employee/property and shall post watch and guard as may be required by the Engineer-in-charge.
- (3) The Contractor shall employ adequate number of technically qualified personnel as per Central Government/CPWD Rules for proper supervision of the work.
- (4) The technical staff should be available at the site, whenever required by NIELIT Calicut to take instructions.
- (5) In case the contractor fails to employ these technical staff as aforesaid he shall be liable to pay a reasonable amount not exceeding Rs.750/- for each month of default.
22. The work shall be carried out as per the drawing showing the layout of internal electrical installation. The NIELIT Calicut reserves the right to make any changes or modifications in the layout. No claim from the contractor on account of any change in layout shall be entertained by NIELIT Calicut.
23. The Contractor shall prepare necessary drawings for approval from Electrical Inspectorate.
24. NIELIT Calicut is not bound to accept the lowest quotation and the accepting officer may reject in part or in full or all the quotations without assigning any reasons.
25. In the event of any dispute, the decision of the accepting officer shall be final and binding on all concerned.
26. Statutory taxes/levies, viz., Income Tax, GST etc. shall be deducted at source as per the prevailing rules.
27. The contractor shall comply with the requirements of all the prevailing tax laws in force such as Income tax act, GST etc.


For NIELIT CALICUT

Date: 9/3/2023

The above terms and conditions accepted

(Signature, Name and Address of the Contractor)

Date:

NIELIT CALICUT
GSTIN : 32AAATD0315M1Z6
Post Box No. 5, P. O. NIT Campus
CALICUT – 673601, Kerala
Tel.: 0495-2287266, 2287166

Providing Acoustic Panelling and Electrical wiring requirements for content for Smart Lab Project in room no.: 225, NIELIT Main campus

Sl No	Description	Unit	Quantity	Rate	Amount in RS. Ps	Remarks
	<u>CIVIL WORK</u>					
1	<u>Acoustic Work:</u> Installation of Acoustic wall with insulation of 500 GSM polyester waddings, fixing with 2ft X 2ft Fulton gypsum tile with ISI make Galvanised iron section (perimeter, intersection, angles etc.). Providing clear putty finish at all joints, Primer and painting with branded paints. Including cost and conveyance of all materials and labour charges etc complete.	SQFT	545.00			
2	<u>GI Frame Work :</u> Providing and fixing 1.5" x 1.5", 16 gauge GI square pipe frame work with suitable flanches and accessories on existing wall for fixing proposed gypsum ceiling including one coat metal primer and two coat enamel paint etc. Cost and conveyance of all materials and labour charge.	KG	105			
3	<u>Ceiling Gypsum Work:</u> Installation of ceiling with insulation of 500 GSM polyester waddings, fixing 2ft X 2ft Fulton gypsum tile with gypsum board on borders with ISI make Galvanised iron section (perimeter, intersection, angles etc.). Providing clear putty finish at all joints, Primer and painting with branded paints. Including cost and conveyance of all materials and labour charges etc complete.	SQFT	200.00			
4	<u>Window Work:</u> Providing Acoustic proof for Glass window with Marine Plywood (18mm) shutters frames, with multiwood shutters with same pattern CNC cutting. Including cost and conveyance of all materials and labour charges etc complete	SQFT	14.00			
5	<u>Main Entrance Door :</u> Outer door opening towards outside in the proposed room and inner door toward inside the same room. Also existing door frame should be covered with plywood and wall carpet. Outer Door: Making outer door with good quality marine plywood and outer surface of the same covered with Mat type Mica finishing and inner surface covered with 1 mm normal wall carpet with good quality door closure, hinges, stopper, lock & Key system etc.. Inner Door: Making Inner door (Total width 100mm thickness) with good quality marine plywood of 12mm thickness outer surface	No	1 (Double door)			

Providing Acoustic Panelling and Electrical wiring requirements for content for Smart Lab Project in room no.: 225, NIELIT Main campus

	should be filled with sufficient quantity 500 GSM polyester waddings. Both sides should be neatly covered with 1 mm thick normal wall carpet. Approximate gap between the two doors should be 20cm. Including cost and conveyance of all materials and labour charges etc complete.					
6	Back Screen: Making of Back screen with good quality marine plywood with proper frame structure and should be filled with insulation of 500GSM polyester waddings. Back screen surface should be super finished with clear putty work and minimum 3 coat good quality Green video paint. Including cost and conveyance of all materials and labour charges etc complete.	SQFT	76.00			
	<u>ELECTRICAL WORK</u>					
	STUDIO LIGHT					
1	Supplying and Wiring light points (studio Light) with 2 X 1.5 sq.mm PVC copper wire including 1 sq.mm earth wire in suitable ISI make PVC conduit with accessories and one no 2 MD 16 Amps modular switch and plate Wire(preferably Finolex, V-guard) Switches& accessories (Preferably Legrand Myris, Legrand My Link)	MTR	10.00			
2	Supplying and fixing ISI branded LED light fittings(23 w X 4 No's studio lights with Pantograph Mechanism) in each unit.	NOS	3			
	CEILING LIGHT					
3	Supplying and Wiring Ceiling light points with 2 X 1.5 sq.mm PVC Copper wire including 1 sq.mm earth wire in suitable I SI make PVC conduit with accessories in 3 loop controls(3 Switches) with 1 no 5 Amps 5 in One Modular Plug sockets and switch in 6 MD modular plate. Wire(preferably Finolex, V-guard) Switches& accessories (Preferably Legrand Myris, Legrand My Link)	MTR	35			
4	Supplying and fixing ISI branded Panel LED light fittings (15 Watts Round type) Preferably Philips, Wipro, Crompton, Siska)	NOS	6			

NIELIT CALICUT
GSTIN : 32AAATD0315M1Z6
 Post Box No. 5, P. O. NIT Campus
 CALICUT – 673601, Kerala
 Tel.: 0495-2287266, 2287166

**Providing Acoustic Panelling and Electrical wiring requirements for content for Smart Lab Project in room
 no.: 225, NIELIT Main campus**

	PLUG POINTS					
5	Supplying and Wiring Plug points with 2 X 2.5 sq.mm PVC copper wire including 1 sq.mm earth wire in suitable ISI make PVC conduit with accessories and individual control. Wire(preferably Finolex, V-guard)	MTR	15			
6	Supplying and Fixing Modular Plug sockets with modular switches without enclosures (8 MD Plate only 3nos, 16 amps 5 in one plug socket, 2nos 16 Amps switch) (Preferably Legrand Myris, Legrand My Link)	NOS	3			
	AC FIXING					
7	Supplying and fixing 2 MD modular plate with 32 Amps DP Switch	NO	1			
8	Re fixing the existing indoor AC unit and stabilizer on Acoustic panel with materials.	NO	1			
	Total Amount					
	Discount if any					
	GST					
	Any other taxes					
	TOTAL AMOUNT -Including all charges (In figures & words)					
	Payment terms					
	Time required to complete the work					
	Quotation validity					
	Warranty					
	Others , if any					
	PAN/GST Registration No, if any					
	Email ID					
	Mobile No.					

NIELIT CALICUT
GSTIN : 32AAATD0315M1Z6
Post Box No. 5, P. O. NIT Campus
CALICUT – 673601, Kerala
Tel.: 0495-2287266, 2287166

**Providing Acoustic Panelling and Electrical wiring requirements for content for Smart Lab Project in room
no.: 225, NIELIT Main campus**

- NB: Contractor may visit the site and inspect before quoting to know the actual site condition**
യഥാർത്ഥ സൈറ്റ് അവസ്ഥ അറിയാൻ കരാറുകാരന് സൈറ്റ് സന്ദർശിക്കേണ്ടതാണ്
- NB: The work inclusive of all material and labour**
തുക എല്ലാ മെറ്റീരിയൽസ് ചാർജും ലേബർ ചാർജും ഉൾപ്പെടുത്തി ആയിരിക്കണം
- NB: The work will be carried out on measurement basis.**
വർക്ക് അളവ് അടിസ്ഥാനത്തിലായിരിക്കും കണക്കാക്കുക
- NB:TDS IT/GST will be deducted as per rules**
- NB: Material and colour of the item will be selected by the centre.**
മെറ്റീരിയലും കളറും സെന്റർ തീരുമാനിക്കുന്നത് വേണം ഉപയോഗിക്കാൻ.
- NB: List of suppliers should be attached.**

(Name & Address with Signature of Contractor)