

5(137) / 2017 / MPW /

Date: 18-09-2020

NOTICE INVITING TENDER

Sealed item rate quotations are invited for LATTICE TYPE TOWER WIND MILL FOUNDATION CONCRETE WORK AND CABLE LAYING WORK IN CAMPUS-1 NIELIT CALICUT. The work to be subscribed on the envelope with the reference No. and due date. The quotations as accompanied with EMD of **Rs. 1450.00/- (Rupees One thousand four hundred and fifty only)** in the form of Online deposit slip / Net banking / CDM deposit to NIELIT account (**Account No 10401158037, SBI NITC branch, IFSC SBIN0002207**) or demand draft drawn in favour of the Director, National Institute of Electronics and Information Technology, Calicut (payable at State Bank of India, NITC Branch) should reach to the office of the Executive Director, National Institute of Electronics and Information Technology, NIT Campus Post, Calicut-673601, **On or before 01.00 PM of 30-09-2020** and will be opened at **2.00 PM** on the same day in the presence of the tenderers who wish to be present. The Quotation not accompanied with EMD shall be rejected.



18/9/20

For EXECUTIVE DIRECTOR

- Encl: 1. Schedule of work
2. Terms and conditions
3. Location and structural drawings

NIELIT CALICUT

GSTIN : 32AAATD0315M1Z6

Post Box No. 5, P. O. NIT Campus

CALICUT – 673601, Kerala

Tel.: 0495-2287266, 2287166

SCHEDULE FOR LATTICE TYPE TOWER WIND MILL FOUNDATION CONCRETE WORK AND CABLE LAYING WORK

Sl No.	REINFORCED CEMENT CONCRETE	Length In meter	Width In meter	Depth In meter	Numbers	LxWxDxNo's In cubic meter	Quantity of work in cubic feet/feet	Charges/Rate Per unit Rs.(per cubic ft/ft as applicable)	Amount
1	Earth excavation മണ്ണ് കുഴിക്കൽ	1.37	1.37	1.47	1	2.997	106		
		0.3	0.3	0.66	4				
2	40 mm aggregate + River sand filling 40 മില്ലി മീറ്റർ ചരൽ കല്ല് + പുഴ മണലും നിറക്കുക	1.37	1.37	0.3	1	0.563	20		
3	Sand filling മണൽ നിറയ്ക്കൽ	1.37	1.37	0.15	1	0.282	10		
4	PCC 1:4:8(1 cement: 4 coarse sand: 8 graded stone aggregate). പിസിസി 1: 4: 8 (1 സിമന്റ്: 4 നാടൻ മണൽ: 8 ഗ്രേഡുളള കല്ല്).	1.37	1.37	0.1	1	0.206	7		
		0.3	0.3	0.05	4				

